

OBIGGS Utilization In Inaccessible Areas

Steve Summer
Project Engineer
Federal Aviation Administration
Fire Safety Branch



Federal Aviation
Administration



International Aircraft Systems Fire
Protection Working Group
Atlantic City, NJ
October 25, 2006


Background

- The FAA recently has released an NPRM requiring the reduction of flammability within heated fuel tanks (affecting over 3,200 in service aircraft)
- The most likely method of conformance is the utilization of an On Board Inert Gas Generating System (OBIGGS)




Background

- CAA Paper 2002/01 (FAA Reference DOT/FAA/AR-02/50) determined that 90% of non-survivable hidden area fires could be prevented if extinguished within 8 minutes



Background

- With inerting systems now/soon to be on board, an integrated fire protection system to provide protection for these hidden areas may be feasible
- Such a system would provide enhanced fire protection while utilizing a system already installed, thus saving on cost, weight and space on board the aircraft



OBJECTIVES

- Design and install an NEA distribution system for fire protection of the overhead area of the FAAs 747SP and 737 test articles
- Examine the effect of various conditions on the ability of the OBIGGS to successfully protect the overhead area:
 - Bleed air pressure
 - OBIGGS feed pressure
 - OBIGGS back pressure
 - Permeate pressure (altitude)
 - Ventilation
 - Etc.
- Future work may include expanding the OBIGGS system to other hidden areas aboard the aircraft (E/E bays, wheel wells, etc.)



TEST ARTICLES

- 747SP equipped with OBIGGS installed in the empty pack bay utilizing up to 6 ASMs
- 737 aircraft in process of being equipped with a single ASM OBIGGS



- Instrumentation allowing for monitoring of oxygen at 12 locations in overhead area of each aircraft
- NEA flow and purity also measured as well as various system pressures

TEST CONFIGURATION – 747SP





TEST SECTION – 747SP



- Located at approximately STA 1241
- Approximately 20 ft. wide, 5 ft. tall at center
- Cross-sectional area of approximately 42 ft²

TEST CONFIGURATION – 737



TEST SECTION – 737



- Approximately 9 ft. wide, 10 in. tall at center
- Cross-sectional area of approximately 3 ft²

CURRENT STATUS

- Preliminary testing on 747SP with a single NEA deposit location has confirmed the need for a vacuum source (or other method) to control the spread of NEA
- Vacuum pump has been installed in forward cargo bay of 747SP and is plumbed to test section
 - We are awaiting electric hookup for the pump before we can begin testing
- OBIGGS and test instrumentation build up on 737 is underway